| ESTIMATE | #21974 |
|---|---|
| TOTAL | $10,770.00 |

## Pro United HVAC

Bryon Finke
4714 West Lake Street
Chicago, IL 60644

(847) 910-7118
bryon.finke@gmail.com

CONTACT US

1024 Dodge Avenue
Evanston, IL 60202

(847) 877-4822
prounitedhvac@gmail.com

# ESTIMATE

| Services | qty | unit price | amount |
|---|---|---|---|
| Ductwork Installation<br>All ductwork will be designed and installed professionally to meet all manufacturers specifications and all local building codes | 1.0 | $5,500.00 | $5,500.00 |
| Furnace Box<br>Return Air Box with Filter Rack, Length: same as furnace Width: same as furnace Height: same as furnace , Gauge Size: 24 ga, | 1.0 | $185.00 | $185.00 |
| Heil 80% Furnace<br>•Quiet performance<br>•Multi-speed blower motor and single-stage gas valve also provide even levels of temperature control and comfort<br>•Dual fuel capable with a compatible heat pump and thermostat for energy-saving heating performance<br>•Low NOx models available (N80ESL)<br>•Air purifier and humidifier compatible<br>•10-Year Parts Limited Warranty upon timely registration+<br>•20-Year Heat Exchanger Limited Warranty | 1.0 | $3,500.00 | $3,500.00 |
| Refrigeration Lines<br>This double insulated tubing transfers refrigerant efficiently between your outdoor condenser and indoor unit | 1.0 | $300.00 | $300.00 |
| Thermostat Wiring | 1.0 | $135.00 | $135.00 |

Thermostat is a sensitive task when installing it if done incorrectly shorts and electrical damage can be done to the unit.

| | | | |
|---|---|---|---|
| ProSelect Thermostat | 1.0 | $165.00 | $165.00 |
| Pro Select thermostat single stage heat and cool | | | |
| Wet Switch Flood Detector | 1.0 | $210.00 | $210.00 |
| The wet switch flood detector is a solid state control designed to help prevent flooding, damage to carpets, walls, furniture, ceilings, etc. It now has a built-in test and reset button for easier installation. It turns the system off when moisture due to condensate or drain leaks is detected. One or two drops will cause Wet Switch to turn off a unit, alerting a serviceman to a moisture problem. A lit LED indicates the Wet Switch is activated and has turned the unit off. Re-set simply by drying the absorbent pad with a paper towel and pressing the reset switch. | | | |
| Drain Pan | 1.0 | $0.00 | $0.00 |
| A drain pan prevents in a scenario where water would pour down through the floor this pan will contain the water and with a float switch or wet switch to stop the HVAC System. | | | |
| Evaporator Cooling Coil | 1.0 | $775.00 | $775.00 |

•Constructed of aluminum fins bonded to internally grooved copper tubing.
•Coils are tested at the factory with an extensive refrigerant leak check.
•Coils have sweat refrigerant connections. Ideally suited for new installations or add on air conditioning.
•Feature two sets of 3/4" [14.1 mm] N.P.T. •Condensate drain connections for ease of connection.
•Coils are AHRI certified for system application with variety of Rheem outdoor units.
•Condensate drain pan is constructed of high grade, heat resistant, corrosion free thermal-set material.
•Compatible with Germicidal Light System (UV resistant)
•Bi-Directional airflow eliminates the need to switch any internal components from horizontal left to right.
•Unique drain pan design maximizes application flexibility and condensate removal.
•Universal Duct Flanges are included with all coil models.

Services subtotal: $10,770.00

| | |
|---|---|
| Subtotal | $10,770.00 |
| **Total** | **$10,770.00** |

This proposal is to install the furnace and ductwork and to make the Air conditioner fully functional.